No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
8	Roofing with hollow or solid reinforced concrete beams and slabs 1 : 2 : 4 with ceiling flush, with bottom flanges of girder spaced about 8′ apart to take a super load of 80 lbs., with ceiling plastered as per design with coving and offsets and on top with surki concrete 4″ thick with two coats of flat tiles plastered smooth complete ..	Sqr.		59·15	
9	Providing sky-lights to the halls with glass panes at the top of roof level as per section..	,,	..	1·60	
10	Skirting of 1″ thick cement concrete 1 : 2 : 4 with topping of ¼″ red cement 9″ high for interior walls as per design ..	R.ft.		834	
11	R.C.C. chajja over windows 4″ thick 4′ width with an anchorage of 1½′ into the walls as per design ..	Sq.ft.		1,034	
12	Teakwood hand railing with wrought iron, flat and square, vertical bars with top and bottom rails 3″×5″ including Duco finish for hand rails ..	R.ft.		79	
13	Plain parapet wall 9″ thick 1½′ to 2′ high as per design including plastering with chunam mortar and white washing, etc., complete ..	R.ft.		264	
14	Providing and fixing cast iron down water pipes of 4″ dia, with suitable bends, etc., complete ..	R.ft.		840	
15	Providing and fixing teakwood doors with frames 3″×5″ without bottom cills having ⅓ panelled ⅔ glazed (Pilkingtons pin-headed ⅛″ glass) 1½″ thick shutters including acme fittings, rim door locks with handles, three finger plates 12″×4″ as per design with six, 6″ steel tipped brass hinges two 6″ hooks brass screws, barrel bolts of suitable size, etc., including delux varnish two coats ..	Sq.ft.		572	
16	Providing and fixing teakwood windows 3″×5″ thick frames with 1¼″ thick glazed shutters in four halves with iron bars ¾″ dia. at 4″ apart including brass fittings, hooks, 2″ rings and casements adjusting stays, etc., complete including two coats of delux varnish ..	,,		455	
17	Providing and fixing teakwood ventilators 3″×4″ thick with 1¼″ thick glazed shutters in two halves with fittings as in item No. 16.	,,		18	
18	Cement perforated ventilators as per design 1½″ thick with 2″×2″ framework above windows ..	,,		40	

M. A. RAMANUJAM,
Assistant Engineer.

KRISHNARAJSAGAR DIVISION.

Notice dated 17th March 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Krishnarajsagar Division, Krishnarajsagar, up to 2 P.M., on Saturday the 9th April 1938, for Constructing Revenue Sub-Division Officer's Quarters at French Rocks.

2. Tenders in the prescribed form, obtainable from the Office of the Executive Engineer, Krishnarajsagar Division, should be addressed to the Executive Engineer, Krishnarajsagar

Division, in a sealed cover and superscribed as "Tender for constructing Revenue Sub-Division Officer's Quarters at French-Rocks.". The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury chellan for a deposit of rupees four hundred (Rs. 400) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. On acceptance of tender, the successful tenderer will have to make a security deposit up to 10 per cent of the estimated value of work which is about Rs. 7,800. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 4th April 1938 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, Krishnaraj Sagar Division, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931), and Mysore Public Works Department specifications.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Krishnaraj Sagar, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rs. 10 (ten).

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of Rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, or estimated, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of September 1938, failing which the Executive Engineer may, at his discretion, levy a penalty per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstanding for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive

Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide power mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Provide his own machinery and pipes, etc., for water-supply and supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and bailing of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Only Mysore Teak selected and purchased from Mysore Government Depots should be used.

Abstract estimate for constructing Revenue Sub-Division Officer's Quarters at French-Rocks.

Sl. No.	Items of work	Per	Estimated rate	Quantity	Cost	Rates to be	
						In figures	In words
	1. *Main Building.*		Rs. a. p.		Rs.		
1	Earthwork excavating foundation and filling in basement	C.yd.	0 4 0	67	17		
2	Filling in foundation with size stone in clay with bond stones at every 5 feet	C.ft.	0 2 6	1,820	284		
3	Filling in basement with size stone in sand mortar with bond stones at 6′ apart	,,	0 4 3	915	243		
4	Burnt brick in clay	,,	0 2 9	3,628	624		
5	Burnt brick in mortar	,,	0 4 0	1,061	265		
6	Burnt stone slabs 6″ thick dressed and fixed	S.ft.	0 6 0	731	274		
7	Providing and fixing teakwood doors with panelled shutters and 3″ to 4″ thick frames, hinges, Tower bolts, catches and staples, etc., complete ..	,,	1 4 0	172	215		
8	Teakwood battened doors, with hinges, bolts, hasps, etc., complete ..	,,	1 2 0	108	122		
9	Teakwood windows with half panelled and half glazed shutters and ¾ round iron bars, rings, etc., complete	,,	1 10 0	141	229		
10	Teakwood battened windows with ¾″ round iron bars, etc., complete	,,	1 8 0	88	132		

Sl. No.	Items of work	Per	Estimated rate	Quantity	Cost	Rates to be	
						In figures	In words
			Rs. a. p.		Rs.		
11	Teakwood wall shelves with 1″ thick battened shutters, hinges, rings, padlocks, hasps, etc., complete with layers of plank	S.ft.	1 2 0	74	83		
12	Rectangular glazed ventilators with wire gauze pattern	,,	1 4 0	36	45		
13	Teakwood circular glazed ventilators	,,	1 8 0	6	9		
14	Archwork over circular ventilators in burnt brick in mortar	C.ft.	0 6 0	12	5		
15	Burnt stone pillars with base and capitals including 2 lines of dressing and edges chamferred complete	Each.	12 0 0	10	120		
16	Providing, hoisting and fixing steel joists 6×3 inches including Railway freight, cutting charges and painting, etc., complete	Cwt.	11 0 0	23	253		
17	Jack arch terrace 9″ thick with two courses of flat tiles and plastering on both sides	Sqr.	40 0 0	4·62	185		
18	Teakwood work wrought and put up with wood oiling complete	C.ft.	5 0 0	110·44	552		
19	Roofing with 1st Class Mangalore tiles on teak reepers 2×1 inches thick with wood oiling to reepers	Sqr.	28 0 0	20·95	587		
20	Ridge tiles set in mortar and painted with cement	R.ft.	0 6 0	104	39		
21	Providing and fixing zinc sheet for valleys with ½″ thick plank at bottom and cement pointing	,,	0 14 0	14	12		
22	Flooring with 3 inches Vajragare and cement plastered	Sqr.	14 0 0	14·37	201		
23	Flagging with burnt stone slabs over 3 inches sandy bed and cement pointing	,,	25 0 0	3·10	78		
24	Plastering with chunam mortar	,,	3 0 0	91·07	273		
25	Masonry parapet wall over terrace 4½″ thick and 1½″ height with pillasters including plastering complete	R.ft.	0 8 0	71	36		
26	Cornice work 12″ thick alround terrace	,,	0 9 0	71	40		
27	Cornice work 6″ thick below Mangalore tiled roof	,,	0 6 0	125	47		
28	Constructing mortar bands over roof with cement rendering	R.ft.	0 3 0	214	40		
29	Constructing sinks in bath and kitchen	Each	..	2	10		
30	Providing mortar and pestle	,,	..	2	10		
31	White washing 2 coats	Sqr.	0 2 9	91·07	16		
32	Teakwood ornamental railing in front verandah with woodoiling, etc.	S.ft.	1 4 0	26	33		
33	Ornamental mouldings over-windows, in front panelling	L. S.	..	..	25		
34	Painting and boxing girders for entablature wall	,,	..	..	50		
35	Nine inches coping over compound wall of open yard with plastering complete	R.ft.	0 6 0	23	9		
36	Cement painting to basement	Sqr.	4 0 0	4·85	19		
37	Chacolate painting 2 coats	,,	3 8 0	10·92	38		
38	Providing zinc sheet down water pipes 3″ dia. wherever necessary	L. S.	..	..	25		

Sl. No.	Items of work	Per	Estimated rate	Quantity	Cost	Rate to be	
						In figures	In words
			Rs. a. p.		Rs.		
39	Providing ornamental eave board to corridor 9″×1″ with painting complete	R.ft.	0 9 0	53	30		
40	Providing ordinary eave board 9″×1″ thick with painting complete ..	,,	0 7 0	99	43		
41	Providing teakwood finials	Each.	1 8 0	2	3		
42	Do do pendents ..	,,	1 0 0	8	8		
43	Providing teakwood racks in stone pillars and wall fixtures	L. S.	..	..	35		
44	Sundry and unforeseen works, such as wood oiling to wall shelves and other items if found necessary	L. S.	..	..	16		
	Total ..	..			5,380		
	II. Out House with Garage and Stables.						
1	Earthwork excavating foundation and filling in basement	C.yd.	0 4 0	15	4		
2	Size stone in mud for foundation ..	C.ft.	0 2 6	393	61		
3	Size stone in mortar for filling in basement	,,	0 4 3	131	35		
4	Burnt brick in mud	,,	0 2 9	1,457	250		
5	Burnt brick in mortar	,,	0 4 0	60	15		
6	Providing and fixing teakwood door to servant's room with hinges, etc., complete	S.ft.	1 2 0	18	20		
7	Teakwood frame with zinc sheet covering with hinges, bolts with washers, etc., complete for garage door ..	S.ft.	0 10 0	76	48		
8	Teakwood bettened windows with round iron bars, etc., complete	,,	1 8 0	19	28		
9	Burnt stone slabs 6″ thick dressed and fixed	,,	0 6 0	118	44		
10	Flooring the servant's room with 3″ Vajragare and ½″ cement plastered ..	Sqr.	14 0 0	3·18	45		
11	Flooring with gravel 4″ thick with watering and tamping	,,	0 12 0	3·00	2		
12	Plastering with chunam mortar ..	,,	3 0 0	24·22	73		
13	White washing two coats	,,	0 2 9	24·22	4		
14	Painting garage door with silicate painting 2 coats	,,	3 8 0	2·56	9		
15	Teakwood work wrought and put up with woodoiling 2 coats ..	C.ft.	5 0 0	44·81	224		
16	Fixing double headed rails with carthire lifting and loading, etc., complete	R.ft.	1 0 0	88	88		
17	Roofing with 1st Class Mangalore tiles over teak reepers with woodoiling to reepers	Sqr.	28 0 0	12·09	338		
18	Providing and fixing ½″ teakwood planking and plain zinc sheet and cement pointing with mortar bands in valley	R.ft.	0 14 0	50	44		
19	Providing mortar bands over roof ..	,,	0 3 0	64	12		
20	Ridge tiles set in mortar and pointed with cement	,,	0 6 0	70	26		
21	Providing and fixing teakwood finials and pendents	Each	0 8 0	10	5		

Sl. No.	Items of work	Per	Estimated rates	Quantity	Cost	Rate to be	
						In figures	In words
22	Providing and fixing mortar and pestle to servant's room		..	1	5		
	Total ..				1,380		
	III. Constructing one Latrine 4′×5′ complete	L. S.	..	..	60		
	IV. Providing and fixing electric lights with connections, switches, lights and casing, etc., complete	,,	..	..	200		
	V. Providing water connections ..	,,	..	..	200		
	VI. Providing drains in the premises, cleaning site and levelling ground ..	,,	..	..	50		
	VII. Constructing compound wall all-round the building with gate and door way	,,	..	..	250		
	VIII. Land acquisition charges (to be done departmentally)	,,	..	..	150		
	Total ..				7,670		
	Contingencies (Reserved) ..				130		
	Total Cost ...				7,800		

G. SESHAGIRI RAO,
Executive Engineer.

ELECTRICAL DEPARTMENT.

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHT, MYSORE.

Notification dated 16th March 1938.

Sealed Tenders for Carting 600 S.M. Rails, 30 feet long, 50 lbs. section, from Forbes Transformer Station, Narasimharaja Mohalla, Mysore, to T.-Narasipur, to be dumped at various points half a mile away from the road-side marked along the route, will be received in the Office of the Superintendent, Mysore Power and Light, Mysore, till 3 P.M., on 8th April 1938.

Tenders should be in triplicate, addressed to the Superintendent, Mysore Power and Light, and should be enclosed in sealed cover and superscribed "Tender for Carting S.M. Rails, 30 feet long, to be opened at 3-30 P.M., on 8th April 1938."

Tenders must be accompanied, under separate cover, either by Registered Post or Money Order or personally, with a deposit of Rs. 25 as otherwise the tender will not be considered.

The successful tenderer will be required to sign the contract deed.

The rates to be tendered in the columns noted below should be entered in figures as well as in words. When once the tender is accepted, no special rate is allowed on any representation for special consideration.

Payment will be made on bills prepared and submitted by the contractors on special printed forms, once in a month.

The loading and un-loading of rails should be arranged to be done by the contractor himself. The decision of the Superintendent, Mysore Power and Light, for all cartings done, will be final in all cases of doubt.

If the rails are not promptly carted, he will be liable for the loss incurred by the Department in getting the work done by other agencies.

The carting contractor should be in touch with the subordinate, in charge of the Electrification Works of T.-Narasipur or the Superintendent, Mysore Power and Light